

100% PROJECT MANUAL

COMMERCE 2.0 MGD GROVE CREEK WPCP

COMMERCE, GEORGIA

for

CITY OF COMMERCE

BID DOCUMENTS

March 2025



Prepared By



Goodwyn Mills Cawood, LLC
6120 Powers Ferry Road NE
Suite 200
Atlanta, GA 30339
T: 770.952.2481
www.gmcnetwork.com

GMC PROJECT NUMBER: CATL230033



OWNERSHIP OF DOCUMENTS AND DISCLAIMER

The Project Manual, Technical Specifications, Drawings, and all other documents relating to this project have been prepared for this individual and particular project, and for the exclusive use of the original Owner, developer or other party so indicated.

Actual project conditions and as-built conditions may vary significantly. Changes made during bidding, negotiations, construction, due to additions or deletions of portions of this project, and/or for other reasons, may not be indicated in these documents.

These documents may not be used or relied upon as a certification of information indicated, or used for any other project, by any third parties or other parties, for any purpose whatsoever, without the prior written consent of Goodwyn Mills Cawood, LLC, or prior to receipt of mutually agreed to compensation paid to Goodwyn Mills Cawood, LLC, therefor.

The ownership, copyrights, and all other rights to these documents, are reserved by Goodwyn Mills Cawood, LLC, including in part, all copies thereof in any form or media. Reproduction of the material contained in these documents or substantial quotation of their provisions without prior written permission of Goodwyn Mills Cawood, LLC, violates the copyright and common laws of the United States and will subject the violator to legal prosecution.

Goodwyn Mills Cawood, LLC
Post Office Box 242128
Montgomery, AL 36124-2128
and
Birmingham, Alabama
Andalusia, Alabama
Auburn, Alabama
Daphne, Alabama
Eufaula, Alabama
Huntsville, Alabama
Mobile, Alabama
Vernon, Alabama
Lutz, Florida
Orlando, Florida
Pensacola, Florida

Sarasota, Florida
Tampa, Florida
Atlanta, Georgia
Augusta, Georgia
Brunswick, Georgia
Cartersville, Georgia
Savannah, Georgia
New Orleans, Louisiana
Charlotte, North Carolina
Charleston, South Carolina
Columbia, South Carolina
Greenville, South Carolina
Brentwood, Tennessee
Nashville, Tennessee

ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ GEOTECHNICAL ■ INTERIOR
DESIGN LANDSCAPE ARCHITECTURE ■ PLANNING ■ SURVEYING ■ TRANSPORTATION

**COMMERCE 2.0 MGD GROVE CREEK
WATER POLLUTION CONTROL PLANT**

FOR

CITY OF COMMERCE

COMMERCE, GEORGIA

GMC PROJECT NO. CATL230033

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>
<u>DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS</u>	
00 10 00	Advertisement for Bids
00 20 00	Instructions to Bidders
00 25 00	Instructions for Submitting Bid Proposals
00 32 00	Information Available to Bidders
00 32 00	Grove Creek WPCP - Geotechnical Report
00 41 13	Bid Form
00 43 13	Bid Bond
00 45 13	Qualifications Statement
00 48 00	Noncollusion Affidavit
00 49 00	Immigration and Security Form
00 51 00	Notice of Award
00 52 13	Agreement between Owner and Contractor for Construction Contract
00 55 00	Notice to Proceed
00 61 13.13	Performance Bond
00 61 13.15	Payment Bond
00 62 76	Application for Payment
00 63 63	Change Order
00 65 16	Certificate of Substantial Completion
00 72 00	General Conditions of the Contract for Construction
00 73 00	Supplementary Conditions
00 85 00	GEFA-SRF-Supplemental - General-Conditions
00 85 50	SLFRF ARPA - Water Sewer Infrastructure Terms and Conditions

DIVISION 01 – GENERAL REQUIREMENTS

01 10 00	Summary
01 15 00	Measurement and Payment
01 21 00	Allowances
01 26 00	Contract Modification Procedures
01 29 00	Payment Procedures
01 29 00A	Contractor Progress Lien Waiver
01 29 00B	Subcontractor Progress Lien Waiver
01 31 00	Project Management and Coordination
01 32 00	Construction Progress Documentation
01 32 33	Photographic Documentation
01 33 00	Submittal Procedures
01 40 00	Quality Requirements
01 42 00	References
01 50 00	Temporary Facilities and Controls
01 60 00	Product Requirements
01 70 00	Execution and Closeout Requirements
01 78 23	Operation and Maintenance Data
01 78 39	Project Record Documents
01 79 00	Demonstration and Training
01 81 00	Geotechnical Data

DIVISION 02 – (NOT USED)

DIVISION 03 – CONCRETE

03 20 00	Anchorage in Concrete
03 30 00	Cast-in-Place Concrete
03 39 00	Concrete Curing
03 60 00	Grouting

DIVISION 04 – MASONRY

04 00 10	Unity Masonry Assemblies
----------	--------------------------

DIVISION 05 – METALS

05 12 00	Structural Steel
05 35 15	Cold-Formed Metal Framing
05 40 00	Aluminum Handrail

05 50 00	Metal Fabrications
05 51 19	Metal Grating Stairs
05 52 13	Pipe and Tube Railings
05 53 13	Bar Gratings
05 60 00	Aluminum Hatches

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

06 10 53	Miscellaneous Rough Carpentry
06 16 00	Sheathing
06 60 00	FRP Weir Plates, Scum Baffles and Brackets

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

07 21 00	Thermal Insulation
07 41 13	Standing-Seam Metal Roof Panels
07 42 93	Soffit Panels
07 54 23	Thermoplastic-Polyolefin (TPO) Roofing
07 62 00	Sheet Metal Flashing and Trim
07 84 00	Firestopping
07 92 00	Joint Sealants

DIVISION 08 – OPENINGS

08 11 13	Hollow Metal Doors and Frames
08 51 13	Aluminum Windows
08 71 00	Door Hardware

DIVISION 09 – FINISHES

09 22 16	Non-Structural Metal Framing
09 29 00	Gypsum Board
09 51 13	Acoustical Panel Ceilings
09 96 00	High-Performance Coatings

DIVISION 10 – SPECIALTIES

10 14 00	Signage
----------	---------

DIVISION 11 - 12 – (NOT USED)

DIVISION 13 – SPECIAL CONSTRUCTION

13 10 00	Bypass Pumping
13 31 00	Fiberglass Reinforced Building Enclosure
13 34 23.11	Fabricated Electrical Houses

DIVISION 14 – 22 (NOT USED)

DIVISION 23 – HEATING, VENTILATING, AND AIR CONDITIONING (NOT USED)

DIVISION 24 – 25 (NOT USED)

DIVISION 26 – ELECTRICAL

26 05 00	Common Work Results for Electrical
26 05 19	Conductors
26 05 26	Grounding and Bonding
26 05 33	Raceways and Boxes
26 05 73	Short Circuit/Coordination Study
26 22 13	Low Voltage Transformers
26 24 16	Panelboards
26 27 26	Wiring Devices
26 28 11	Molded Case Circuit Breakers
26 28 16	Safety Switches
26 29 23	Variable Frequency Drives
26 32 13	Generators
26 35 26	Active Harmonic Filter
26 36 23	Automatic Transfer Switches
26 50 00	Lighting

DIVISION 27 – COMMUNICATIONS

27 05 26	Grounding and Bonding for Communications Systems
27 05 28	Pathways for Communications Systems
27 05 28.29	Hangers and Supports for Communications Systems
27 11 00	Communications Equipment Room Fittings
27 13 23	Communications Optical Fiber Backbone Cabling
27 15 13	Communications Copper Horizontal Cabling
27 15 23	Communications Optical Fiber Horizontal Cabling

DIVISION 28 – 30 (NOT USED)

DIVISION 31 – EARTHWORK

31 05 16	Aggregates for Earthwork
31 10 00	Site Clearing
31 20 00	Earth Moving
31 23 16.13	Excavation and Trenching
31 23 16.26	Rock Removal
31 23 19	Dewatering
31 25 00	Erosion and Sedimentation Controls
31 50 00	Excavation Support and Protection

DIVISION 32 – EXTERIOR IMPROVEMENTS

32 05 19	Geosynthetics for Exterior Improvements
32 12 16	Asphalt Paving
32 13 13	Concrete Paving
32 31 13	Chain Link Fence and Gates
32 91 13	Soil Preparation
32 92 00	Turf and Grasses
32 92 19	Seeding and Restoration

DIVISION 33 – UTILITIES

33 01 30.13	Sewer and Manhole Testing
33 01 30.51	Pumping and Bypassing
33 01 30.61	Sewer and Pipe Joint Sealing
33 01 30.62	Manhole Grout Sealing
33 05 05.31	Hydrostatic Testing
33 05 13	Manholes and Structures
33 05 16.13	Precast Concrete Utility Structures
33 05 26	Utility Identification
33 31 00	Sanitary Utility Sewerage Piping
33 41 13	Public Storm Utility Drainage Piping

DIVISION 34 – 39 (NOT USED)

DIVISION 40 – PROCESS INTERCONNECTIONS

40 05 06	Couplings Adapters Specials for Process Piping
40 05 07	Hangers and Supports for Process Piping

40 05 13	Common Requirements for Process Piping
40 05 19	Ductile Iron Process Pipe
40 05 23	Stainless Steel Process Pipe and Tubing
40 05 31	Thermoplastic Process Pipe
40 05 51	Common Requirements for Process Valves
40 05 53	Identification for Process Piping
40 05 57	Actuators for Process Valves and Gates
40 05 59	Aluminum Slide Gates
40 05 62	Plug Valves
40 05 63	Ball Valves
40 05 64	Butterfly Valves
40 05 65.23	Swing and Disc Check Valves
40 05 78.21	Air Release Valves for Wastewater Service
40 42 13	Process Piping Insulation
40 70 00	Instrumentation Devices
40 71 13	Magnetic Flow Meters
40 71 69	Parshall Flume
40 72 13	Ultrasonic Level Meters
40 72 43.00	Pressure and Differential Pressure Type Level Meters
40 72 76	Level Switches
40 73 13	Pressure & Differential Pressure Gauges
40 73 64	Annular Pressure Seals
40 75 00	Refrigerated Auto Sampler
40 75 13	PH ORP Sensors
40 75 43	Fluorescent Dissolved Oxygen Measuring
40 90 00	Instrumentation and Control for Process Systems
40 94 03	Programmable Logic Controller Subsystem (PLCS)

DIVISION 41 - MATERIAL PROCESSING & HANDLING EQUIP

41 15 13	Chemical IBC Tote Scale
41 22 14	Jib Cranes
41 22 24	Electrified Monorail Hoist

DIVISION 42 (NOT USED)

DIVISION 43 – PROCESS GAS AND LIQUID HANDLING, PURIFICATION AND STORAGE EQUIPMENT

43 23 13	Reuse Vertical Turbine Pumps
43 25 13	Submersible Centrifugal Pumps
43 26 13	Submersible Chopper Pumps
43 41 46	Polyethylene Tanks and Accessories
43 53 54	Blowers

DIVISION 44 – 45 (NOT USED)

DIVISION 46 – WATER AND WASTEWATER EQUIPMENT

46 05 53	Identification for Water and Wastewater Equipment
46 21 15	Rotary Drum Screens
46 23 23	Grit Removal Equipment
46 33 41	Liquid Chemical Feed Systems
46 33 83	Liquid Chemical Feed Accessories and Safety Equipment
46 41 26	Floating Mechanical Aerators
46 43 21	Circular Secondary Clarifier Equipment
46 51 15	Orbal Aeration System
46 51 16	Submersible Aspirating Aerator Equipment
46 51 23	Fixed Header Aeration System
46 61 23	Disc Cloth Tertiary Filtration
46 66 16	Non-Contact UV Disinfection Equipment
46 73 22	Decanter Assembly
46 76 21	Belt Filter Presses

DIVISION 47 – 48 (NOT USED)

APPENDIX

State of Georgia DNR/EPD NPDES General Permit No. GAR 100001	1 – 48
State of Georgia DNR/EPD NPDES General Permit No. GAR 100002	1 - 50
State of Georgia DNR/EPD NPDES Fact Sheet	1 – 9
State of Georgia DNR/EPD NPDES Fact Sheet Addendum	1 – 2
NPDES General Construction Permit References	1 Page
Grove Creek WPCP – NPDES GA0050355 Draft Permit Package - City – 2025	56 Pages

SECTION 08 11 13 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes hollow-metal work.
- B. Related Requirements:
 - 1. Section 08 71 00 - Door Hardware for door hardware for hollow-metal doors.

1.3 DEFINITIONS

- A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

1.4 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

1.5 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, temperature-rise ratings, and finishes.
- B. Shop Drawings: Include the following:
 - 1. Elevations of each door type.
 - 2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
 - 3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.

4. Locations of reinforcement and preparations for hardware.
 5. Details of each different wall opening condition.
 6. Details of anchorages, joints, field splices, and connections.
 7. Details of accessories.
 8. Details of moldings, removable stops, and glazing.
 9. Details of conduit and preparations for power, signal, and control systems.
- C. Samples for Initial Selection: For units with factory-applied color finishes.
- D. Samples for Verification:
1. For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches.
 2. For "Doors" and "Frames" subparagraphs below, prepare Samples approximately 8 by 10 inches to demonstrate compliance with requirements for quality of materials and construction:
 - a. Doors: Show vertical-edge, top, and bottom construction; core construction; and hinge and other applied hardware reinforcement. Include separate section showing glazing if applicable.
 - b. Frames: Show profile, corner joint, floor and wall anchors, and silencers. Include separate section showing fixed hollow-metal panels and glazing if applicable.
- E. Schedule: Provide a schedule of hollow-metal work prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final Door Hardware Schedule.

1.7 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: For each type of hollow-metal door and frame assembly, for tests performed by a qualified testing agency.
- B. Oversize Construction Certification: For assemblies required to be fire rated and exceeding limitations of labeled assemblies.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use non-vented plastic.
 1. Provide additional protection to prevent damage to factory-finished units.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch- high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ceco Door
 - 2. Republic Doors and Frames.
 - 3. Steelcraft; an Allegion brand.
 - 4. Or Equal.
- B. Source Limitations: Obtain hollow-metal work from single source from single manufacturer.

2.2 REGULATORY REQUIREMENTS

- A. Fire-Rated Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings and temperature-rise limits indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.
 - 1. Smoke- and Draft-Control Assemblies: Provide an assembly with gaskets listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing according to UL 1784 and installed in compliance with NFPA 105.
- B. Fire-Rated, Borrowed-Lite Assemblies: Complying with NFPA 80 and listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing according to NFPA 257 or UL 9.

2.3 INTERIOR DOORS AND FRAMES

- A. Construct interior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Standard-Duty Doors and Frames: SDI A250.8, Level 1. At locations indicated in the Door and Frame Schedule.
 - 1. Physical Performance: Level C according to SDI A250.4.
 - 2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches.
 - c. Face: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.032 inch.
 - d. Edge Construction: Model 2, Seamless.
 - e. Core: Polyurethane with vertical steel stiffener.
 - 3. Frames:

- a. Materials: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.042 inch.
 - b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
 - c. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.
 - 4. Exposed Finish: Prime, Factory.
- C. Heavy-Duty Doors and Frames: SDI A250.8, Level 2. At locations indicated in the Door and Frame Schedule.
- 1. Physical Performance: Level B according to SDI A250.4.
 - 2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches.
 - c. Face: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.042 inch.
 - d. Edge Construction: Model 2, Seamless.
 - e. Core: Polyurethane with vertical steel stiffener.
 - 3. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch.
 - b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
 - c. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.
 - 4. Exposed Finish: Prime, Factory.
- D. Extra-Heavy-Duty Doors and Frames: SDI A250.8, Level 3. At locations indicated in the Door and Frame Schedule.
- 1. Physical Performance: Level A according to SDI A250.4.
 - 2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches.
 - c. Face: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.053 inch.
 - d. Edge Construction: Model 3, Stile and Rail.
 - e. Core: Core: Polyurethane, vertical steel stiffener.
 - 3. Frames:

- a. Materials: Metallic-coated, steel sheet, minimum thickness of 0.053 inch.
 - b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
 - c. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.
 - 4. Exposed Finish: Prime, Factory.
- E. Hollow-Metal Doors and Frames: NAAMM-HMMA 860. At locations indicated in the Door and Frame Schedule.
- 1. Physical Performance: Level A according to SDI A250.4.
 - 2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches
 - c. Face: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.032 inch.
 - d. Edge Construction: Continuously welded with no visible seam.
 - e. Core: Polyurethane, steel stiffened.
 - 3. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch for frames that receive hollow-metal doors; minimum thickness of 0.042 inch for frames that receive hollow-core wood doors.
 - b. Materials: Metallic-coated steel sheet, minimum thickness of 0.042; inch 0.053 inch.
 - c. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
 - d. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.
 - 4. Exposed Finish: Prime.

2.4 EXTERIOR HOLLOW-METAL DOORS AND FRAMES

- A. Construct exterior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Heavy-Duty Doors and Frames: SDI A250.8, Level 2. At locations indicated in the Door and Frame Schedule.
 - 1. Physical Performance: Level B according to SDI A250.4.

2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches
 - c. Face: Metallic-coated steel sheet, minimum thickness of 0.042 inch, with minimum A40 coating.
 - d. Edge Construction: Model 2, Seamless.
 - e. Core: Polyurethane with vertical steel stiffener.
 - 1) Thermal-Rated Doors: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu when tested according to ASTM C 1363.

3. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
 - b. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.

4. Exposed Finish: Prime Factory.

C. Extra-Heavy-Duty Doors and Frames: SDI A250.8, Level 3. At locations indicated in the Door and Frame Schedule.

1. Physical Performance: Level A according to SDI A250.4.
2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches
 - c. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
 - d. Edge Construction: Model 3, Stile and Rail.
 - e. Core: Polyurethane with vertical steel stiffener.
 - 1) Thermal-Rated Doors: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu when tested according to ASTM C 1363.

3. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
 - b. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.

4. Exposed Finish: Prime Factory.
- D. Hollow-Metal Doors and Frames: NAAMM-HMMA 860. At locations indicated in the Door and Frame Schedule.
 1. Physical Performance: Level A according to SDI A250.4.
 2. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches
 - c. Face: Metallic-coated steel sheet, minimum thickness of 0.042 inch, with minimum G60A60 coating.
 - d. Edge Construction: Continuously welded with no visible seam.
 - e. Core: Steel stiffened.
 - 1) Thermal-Rated Doors: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu when tested according to ASTM C 1363.
 3. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum G60A60 coating.
 - b. Construction:
 - 1) Knock down - for frames in gypsum board partitions, except fire rated frames
 - 2) Full profile welded - frames in masonry and concrete walls, fire rated frames over 7'-0" in gypsum board.
 4. Exposed Finish: Prime.
- 2.5 BORROWED LITES
 - A. Hollow-metal frames of metallic-coated steel sheet, minimum thickness of 0.053 inch.
 - B. Construction: Full profile welded.
- 2.6 HOLLOW-METAL PANELS
 - A. Provide hollow-metal panels of same materials, construction, and finish as adjacent door assemblies.
- 2.7 FRAME ANCHORS
 - A. Jamb Anchors:

1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, not less than 0.042 inch thick, with corrugated or perforated straps not less than 2 inches wide by 10 inches long; or wire anchors not less than 0.177 inch thick.
 2. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
 3. Compression Type for Drywall Slip-on Frames: Adjustable compression anchors.
 4. Postinstalled Expansion Type for In-Place Concrete or Masonry: Minimum 3/8-inch-diameter bolts with expansion shields or inserts. Provide pipe spacer from frame to wall, with throat reinforcement plate, welded to frame at each anchor location.
- B. Floor Anchors: Formed from same material as frames, minimum thickness of 0.042 inch, and as follows:
1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.
 2. Separate Topping Concrete Slabs: Adjustable-type anchors with extension clips, allowing not less than 2-inch height adjustment. Terminate bottom of frames at finish floor surface.

2.8 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Hot-Rolled Steel Sheet: ASTM A 1011, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.
- C. Metallic-Coated Steel Sheet: ASTM A 653, Commercial Steel (CS), Type B.
- D. Frame Anchors: ASTM A 879, Commercial Steel (CS), 04Z coating designation; mill phosphatized.
1. For anchors built into exterior walls, steel sheet complying with ASTM A 1008 or ASTM A 1011, hot-dip galvanized according to ASTM A 153, Class B.
- E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153.
- F. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.
- G. Grout: ASTM C 476, except with a maximum slump of 4 inches, as measured according to ASTM C 143.
- H. Mineral-Fiber Insulation: ASTM C 665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E 136 for combustion characteristics.
- I. Bituminous Coating: Cold-applied asphalt mastic, compounded for 15-mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.9 FABRICATION

- A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.
- B. Hollow-Metal Doors:
 - 1. Steel-Stiffened Door Cores: Provide minimum thickness 0.026 inch, steel vertical stiffeners of same material as face sheets extending full-door height, with vertical webs spaced not more than 6 inches apart. Spot weld to face sheets no more than 5 inches o.c. Fill spaces between stiffeners with glass- or mineral-fiber insulation.
 - 2. Fire Door Cores: As required to provide fire-protection and temperature-rise ratings indicated.
 - 3. Vertical Edges for Single-Acting Doors: Bevel edges 1/8 inch in 2 inches.
 - 4. Top Edge Closures: Close top edges of doors with inverted closures of same material as face sheets.
 - 5. Bottom Edge Closures: Close bottom edges of doors where required for attachment of weather stripping with end closures or channels of same material as face sheets.
 - 6. Exterior Doors: Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
 - 7. Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted or as required to comply with published listing of qualified testing agency.
- C. Hollow-Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
 - 1. Sidelite and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
 - 2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 - 3. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
 - 4. Floor Anchors: Weld anchors to bottoms of jambs with at least four spot welds per anchor; however, for slip-on drywall frames, provide anchor clips or countersunk holes at bottoms of jambs.
 - 5. Jamb Anchors: Provide number and spacing of anchors as follows:
 - a. Masonry Type: Locate anchors not more than 16 inches from top and bottom of frame. Space anchors not more than 32 inches o.c., to match coursing, and as follows:
 - 1) Two anchors per jamb up to 60 inches high.
 - 2) Three anchors per jamb from 60 to 90 inches high.
 - 3) Four anchors per jamb from 90 to 120 inches high.
 - 4) Four anchors per jamb plus one additional anchor per jamb for each 24 inches or fraction thereof above 120 inches high.

- b. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
 - 1) Three anchors per jamb up to 60 inches high.
 - 2) Four anchors per jamb from 60 to 90 inches high.
 - 3) Five anchors per jamb from 90 to 96 inches high.
 - 4) Five anchors per jamb plus one additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.
 - c. Compression Type: Not less than two anchors in each frame.
 - d. Postinstalled Expansion Type: Locate anchors not more than 6 inches from top and bottom of frame. Space anchors not more than 26 inches o.c.
 - 6. Head Anchors: Two anchors per head for frames more than 42 inches wide and mounted in metal-stud partitions.
 - 7. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
 - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
 - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- D. Fabricate concealed stiffeners and edge channels from either cold- or hot-rolled steel sheet.
- E. Hardware Preparation: Factory prepare hollow-metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
 - 1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
 - 2. Comply with applicable requirements in SDI A250.6 and BHMA A156.115 for preparation of hollow-metal work for hardware.
- F. Stops and Moldings: Provide stops and moldings around glazed lites and louvers where indicated. Form corners of stops and moldings with mitered hairline joints.
 - 1. Single Glazed Lites: Provide fixed stops and moldings welded on secure side of hollow-metal work.
 - 2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.
 - 3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.
 - 4. Provide loose stops and moldings on inside of hollow-metal work.
 - 5. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.

2.10 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.
- B. Factory Finish: Clean, pretreat, and apply manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat, complying with SDI A250.3.
 1. Color and Gloss: As selected by Engineer from manufacturer's full range.

2.11 ACCESSORIES

- A. Louvers: Provide louvers for interior doors, where indicated, which comply with SDI 111C, with blades or baffles formed of 0.020-inch- thick, cold-rolled steel sheet set into 0.032-inch- thick steel frame.
 1. Sightproof Louver: Stationary louvers constructed with inverted-V or inverted-Y blades.
 2. Lightproof Louver: Stationary louvers constructed with baffles to prevent light from passing from one side to the other.
 3. Fire-Rated Automatic Louvers: Louvers constructed with movable blades closed by actuating fusible link, and listed and labeled for use in fire-rated door assemblies of type and fire-resistance rating indicated by same qualified testing and inspecting agency that established fire-resistance rating of door assembly.
- B. Mullions and Transom Bars: Join to adjacent members by welding or rigid mechanical anchors.
- C. Grout Guards: Formed from same material as frames, not less than 0.016 inch thick.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for embedded and built-in anchors to verify actual locations before frame installation.
- C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.

- B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.3 INSTALLATION

- A. General: Install hollow-metal work plumb, rigid, properly aligned, and securely fastened in place. Comply with Drawings and manufacturer's written instructions.
- B. Hollow-Metal Frames: Install hollow-metal frames for doors, transoms, sidelites, borrowed lites, and other openings, of size and profile indicated. Comply with SDI A250.11 or NAAMM-HMMA 840 as required by standards specified.
 - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.
 - a. At fire-rated openings, install frames according to NFPA 80.
 - b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
 - c. Install frames with removable stops located on secure side of opening.
 - d. Install door silencers in frames before grouting.
 - e. Remove temporary braces necessary for installation only after frames have been properly set and secured.
 - f. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
 - g. Field apply bituminous coating to backs of frames that will be filled with grout containing antifreezing agents.
 - 2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.
 - a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
 - 3. Metal-Stud Partitions: Solidly pack mineral-fiber insulation inside frames.
 - 4. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with grout.
 - 5. Concrete Walls: Solidly fill space between frames and concrete with mineral-fiber insulation.
 - 6. In-Place Concrete or Masonry Construction: Secure frames in place with postinstalled expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.
 - 7. In-Place Metal or Wood-Stud Partitions: Secure slip-on drywall frames in place according to manufacturer's written instructions.
 - 8. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:
 - a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.

- b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
 - c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.
- C. Hollow-Metal Doors: Fit hollow-metal doors accurately in frames, within clearances specified below. Shim as necessary.
 - 1. Non-Fire-Rated Steel Doors:
 - a. Between Door and Frame Jambs and Head: 1/8 inch plus or minus 1/32 inch.
 - b. Between Edges of Pairs of Doors: 1/8 inch to 1/4 inch plus or minus 1/32 inch.
 - c. At Bottom of Door: 5/8 inch] plus or minus 1/32 inch.
 - d. Between Door Face and Stop: 1/16 inch to 1/8 inch plus or minus 1/32 inch.
 - 2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.
 - 3. Smoke-Control Doors: Install doors and gaskets according to NFPA 105.
- D. Glazing: Comply with installation requirements in Section 08 80 00 - Glazing and with hollow-metal manufacturer's written instructions.
 - 1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

3.4 ADJUSTING AND CLEANING

- A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.
- B. Remove grout and other bonding material from hollow-metal work immediately after installation.
- C. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.
- D. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.
- E. Factory-Finish Touchup: Clean abraded areas and repair with same material used for factory finish according to manufacturer's written instructions.
- F. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION 08 11 13